

MECHANICAL SCOPE

- 1- Remove and turn over to Contractor two existing condensing units located in the cupola mezzanine. Demolish and patch the sheet metal ducting between the condensing unit and the exhaust box.
- 2- Remove and turn over to Contractor four ductless split units, including associated controls, and piping.
- 3- Remove existing steel exhaust register from ticket room, and cap duct work.
- 4- Install a new package air handling unit (specified in drawings) with all associated return and supply ductwork, air devices, two electrical duct heaters, two thermostats, condensate pump, and drain line.
- 5- Provide two metal boxes behind the existing louver in the cupola mezzanine and tie them the return and condenser exhaust of the AHU.
- 6- Startup, test, and balance the Air handling package unit.