

PLUMBING SCOPE OR WORK

- 1- Remove and store for reinstallation the electrical water cooler (EWC) located in the existing vending room.
- 2- Modify the existing EWC drain to install a sink in the new breakroom.
- 3- Modify the cold-water line rough and install a new hot water line for the kitchen sink from item 2.
- 4- Provide and install a 3/8" compression outlet box above the counter.
- 5- Provide new cold-water line to supply the relocated EWC
- 6- Provide and install a new hose bib (to match existing hose bib in break room).
- 7- Provide a new 2" drain line for relocated EWC and connect it to the existing plumbing ventilation system of the building.